

GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Irrigation & CAD Department – APSIDC – Reconstruction of Gondiparla Lift Irrigation Scheme on Tungabhadra River in Gondiparla (V), Kurnool Mandal & District – Administrative approval for an amount of Rs.545.88 lakhs – Orders – Issued.

=====

IRRIGATION & CAD (MIR2) DEPARTMENT

G.O.Rt.No. 943

Dated: 30-08-2012

Read:-

From the VC&MD, APSIDC Ltd., Hyderabad Letter No.IDC/
MD/Tech/KNL/Gondiparla LIS/1078/2012-13, dated
14.6.2012.

ORDER:-

The Vice Chairman & Managing Director, APSIDC., in his letter read above, has submitted proposal for according administrative approval for the work “Reconstruction of Gondiparla Lift Irrigation Scheme on Tungabhadra River in Gondiparla (V), Kurnool Mandal & District for an amount of Rs.577.00 lakhs to irrigate 830 acres (Khariff ID), under State Plan funds. He has also stated that there is no scope of work directly involved towards labour component to take up the works through MGNREGS for the said Lift Irrigation Scheme.

2. After careful examination of the matter, Government hereby accord administrative approval for **Rs.545.88 lakhs** (Rupees five Crores forty five lakhs and eighty eight thousand only) for the work “Reconstruction of Gondiparla Lift Irrigation Scheme on Tungabhadra River in Gondiparla Village of Kurnool Mandal & District for utilization of 37.00 Mcft (14.30 cusecs peak discharge) to irrigate 830 acres of Khariff ID under State Plan funds for the year 2012-13 under head of account 4702 – MH 101 – GH(11) – SH (15) Lift Irrigation works – 530/531. The details of provisions after scrutiny are Annexed to this order.

3. The Vice Chairman & Managing Director, APSIDC Ltd., Hyderabad shall take necessary action accordingly.

4. This order issues with the concurrence of Finance (Exp.PW) Department vide their U.O.No.18931/706/A1/Exp.PW/2012, dated 26.7.2012.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

AJOYENDRA PYAL,
SPECIAL CHIEF SECRETARY TO GOVERNMENT (I).

To
The Vice Chairman & Managing Director, APSIDC Ltd., Hyderabad.
The Superintending Engineer, APSIDC Circle, Kadapa.
The District Collector, Kurnool.
The Pay and Accounts Officer, Kadapa.

Copy to

The Accountant General, A.P., Hyderabad.
The Finance (Exp.PW) Department.
O.S.D. to M(MI,APSIDC,LI,GWD & WALAMTARI)
P.S. to Spl.C.S., I&CAD Dept.
P.S. to Special Secretary (I/C), I&CAD Dept.
Sf/Sc.

// FORWARDED:: :: BY ORDER//

SECTION OFFICER

ANNEXURE TO G.O.Rt.No. 943 I & CAD (MIR) DEPARTMENT, DATED 30-08-2012

Sl. No.	Component	Details of Proposal	APSIDC Norms	Amount Rs. in lakhs
I	Main Provisions			
	a) Pressure Main	700 mm dia of PSC pipes of length 1400 m	No norms fixed. It depends on dia of pressure main and total head to be lifted.	122.36
	b) Jack well cum Pump House	7.00 m internal dia is proposed	No norms fixed. It depends on number of pumps to be installed.	53.05
	c) Pumps including specials	3 Nos x 90 H.P. VT pumps	No norms fixed. It depends on discharge and suction head to be lifted.	36.61
	d) Transformer	1 x 315 KVA Transformer with double pole structure	No norms fixed. It depends on pumps H.P. required.	5.88
	Total			217.90
II.	Other Provisions <u>(Other Civil Minor Works)</u>			
	a) Intake well	2.0 m internal dia with steining thickness of 0.20 m thick in RCC M20 grade concrete.	No norms fixed. It depends upon discharge and site condition.	1.57
	b) intake Pipe line	900 mm dia NP3 class RCC Pipes of length 480 m.	No norms fixed. It depends upon discharge and site condition.	90.78
	c) Delivery Cistern	7.0 m dia in RCC M20 grade thick steining	No norms fixed. It depends upon site condition.	6.08
	d) Gravity Mains	Gravity main DC-1 to DC-2:- 355 mm dia RCC pipes of length 575 m. Gravity main DC-2 to DC-3:- 355 mm dia RCC pipes of length 450 m. Gravity main DC-3 to DC-4:- 355 mm dia RCC pipes of length 570 m. Gravity main DC-4 to DC-5:- 355 mm dia RCC pipes of length 345 m. Gravity main DC-5 to DC-6:- 355 mm dia RCC pipes of length 485 m. Gravity main DC-1 to DC-7:- 355 mm dia RCC pipes of length 360 m. Gravity main DC-7 to DC-8:- 355 mm dia RCC pipes of length 300 m. Gravity main DC-8 to DC-9:- 355 mm dia RCC pipes of length 420 m. Gravity main DC-9 to DC-10:-355mm dia RCC pipes of length 135 m. Gravity main DC-9 to DC-11:-355mm dia RCC pipes of length 475 m. Gravity main DC-7 to DC-12:-355mm dia RCC pipes of length 620 m. Gravity main DC-12 to DC-13:-355mm dia RCC pipes of length 250 m.	No norms fixed. It depends upon discharge required for the ayacut	98.65

	e) Transformer and yard civil works	Erection of double pole structure	No norms fixed. It depends site condition	2.04
	Total			199.12
III.	<u>L.S. Provision:</u>			
	a) VAT	-	@ 5% on works	20.86
	b) Survey, investigation etc.	-	@ Rs.350/- per acre	2.91
	c) Establishment charges	-	@ 15% on works	62.56
	d) Service Line charges payable to A.P.Transco	-	It depends upon the requirement of A.P. TRANSCO.	36.50
	e) Labour cess	-	@ 1% on works	4.38
	f) Tender Publication charges	-	No norms. As per requirement.	1.65
	Total			128.86
	Grand Total (I + II + III)			Rs.545.88 lakhs

AJOYENDRA PYAL,
SPECIAL CHIEF SECRETARY TO GOVERNMENT (I).

// FORWARDED:: :: BY ORDER//

SECTION OFFICER